

TERMS OF REFERENCE

1. PROJECT TITLE

Provision of Internet Access via Low Earth Orbit Satellite (PIALEOS) for Government Support in Barangay Halls and Public Transport Terminals in Region XIII

2. GENERAL INFORMATION

The DICT's Free Public Internet Access Program is a digital empowerment program which aims to connect Filipinos nationwide through the provision of free Wi-Fi in public places in accordance with Republic Act No. 10929, also known as the "Free Internet Access in Public Places Act".

Pursuant to Section 4. of R.A. 10929, Free Public Internet Access Program shall be made available at all government hospitals and health centres; national and local government offices; public libraries; public parks, plazas, and other open areas; public schools; state universities and colleges along with TESDA institutions; and transport terminals across the country.

3. RATIONALE OF THE PROJECT

This Project aims to procure an internet service subscription from the Internet Service Provider (ISP) for the Free Wi-Fi for All Program's public hotspots. The basis of this tender for the PIALEOS for Government Support in Barangay Halls and Public Transport Terminals in Region XIII is Republic Act No. 12009, also known as the "New Government Procurement Act".

Through the provision of reliable and high-speed internet connectivity, the project enables residents, commuters, stakeholders, and the general public to access online information, communication platforms, e-government services, educational content, health information, livelihood opportunities, and other essential digital resources within selected Barangay Halls and Public Transport Terminals across Region XIII. This initiative promotes digital inclusion, enhances access to public services, improves user experience, and helps bridge the digital divide, particularly in remote and geographically challenged areas. Low Earth Orbit (LEO) satellite technology may be utilized to provide fast and reliable internet access without the need for extensive ground infrastructure, allowing faster deployment and wider coverage in hard-to-reach locations. The direct beneficiaries of the project are the general public and community members utilizing the connectivity services in the identified locations throughout Region XIII.

This procurement will be implemented under a managed service arrangement, which includes the supply, delivery, installation, and operations and maintenance (O&M) of Customer Premises Equipment (CPEs), as well as a four (4)-month internet subscription.

The service provider shall ensure continuous monitoring, maintenance, and technical support throughout the project duration to guarantee service reliability and uptime.

Furthermore, the project aims to deploy forty-one (41) Low Earth Orbit (LEO) satellite internet kits across the region, establishing forty-one (41) additional beneficiary locations. Each site shall be equipped with three (3) strategically installed wireless access points (APs), resulting in a total of one hundred twenty-three (123) APs. This initiative will significantly enhance connectivity coverage and accommodate a greater number of users in unserved and underserved communities.

Section 5 (n) of Republic Act No. (R.A.) 12009 defines goods as referring to all items, supplies, materials, and general support services which may be needed in the transaction of public business or in the pursuit of any government undertaking. Such definition necessarily includes the procurement of internet service providers and public utility services, such as water, electricity, telecommunications, and internet services

Rules and Regulations to Implement the Provision of Republic Act No. 10929 (Free Internet Access in Public Places Act) under Section 4: Definition of Terms refers to Internet Service Provider (ISP) as an entity that provides access to and/or internetworking connectivity via the Internet, usually for a monthly fee, and may include other Internet-based value-added services. Meanwhile, Section 6 states that ISPs may acquire and utilize internet connectivity directly from the satellite service and other emerging technology providers, to ensure universal coverage, which, when used to provide internet connectivity, shall be considered a value-added service.

4. MODE AND NATURE OF PROCUREMENT

The basis of this tender for the Project is Competitive Bidding. The nature of this procurement is the Delivery of Goods, which comprises delivery, installation, configuration, testing and acceptance, managed internet service, operations and maintenance, monitoring, and support services. The contract shall be awarded to the bidder who submitted the Lowest Calculated and Responsive Bid (LCRB).

5. APPROVED BUDGET OF THE CONTRACT

- 5.1.** The total cost for this project is **THREE MILLION NINE HUNDRED FORTY-FIVE THOUSAND EIGHT HUNDRED EIGHTY-ONE PESOS ONLY (PHP 3,945,881.00)** covering the internet service subscription, including delivery, installation, acceptance, operation, and maintenance services for the selected Barangay Halls and Public Transport Terminals across the Region XIII.
- 5.2.** Source of funds is the Continuing Fund FY 2025 Special Account in the General Fund - Free Public Internet Access Program.

6. PROJECT DELIVERABLES

- 6.1.** The delivery of the service and installation, including testing and acceptance, to all locations, is thirty (30) calendar days upon receipt of the NTP

- 6.2. Service coverage, meanwhile, shall include SLA and warranty for four (4) months.
- 6.3. Service coverage and warranty shall be until the end of the service coverage and operation provided that applicable service extensions, if any, shall be applied.

7. COMPONENT / LOT BREAKDOWN

Lot No.	Site Type	Coverage Area	Number of Locations	Total No. of Access Points	TOTAL ABC (Php)
1	Barangay Halls	Agusan del Norte; Agusan del Sur; Surigao del Norte; Surigao del Sur	26	78	2,502,266.00
2	Public Transport Terminals	Agusan del Norte; Agusan del Sur; Surigao del Norte; Surigao del Sur	15	45	1,443,615.00

8. SCOPE OF WORK

- 8.1. The Service Provider shall supply, deliver, install, test, and commission a highly secure enterprise-grade Internet access per identified location (Annex A: List of Locations), using Low Earth Orbit (LEO) satellite systems, with the following minimum characteristics, capacities, and/or capabilities:

- 8.1.1. **Internet Connection** – Shall provide an internet connection per location with the following specifications:

- 8.1.1.1. **LEO Satellite Connectivity** (per location)

Download Bandwidth	Upload Bandwidth	Data Allocation per Month	Round Trip Latency
100 - 220 Mbps per location	10 - 25 Mbps per location	Unlimited	Maximum of 60 ms

- 8.1.1.2. Must support IPv4 and IPv6 connectivity with globally routable addresses to ensure interoperability and future-proofing.

8.2. EQUIPMENT REQUIREMENTS

- 8.2.1. The Service Provider shall design, supply, deliver, install, and commission a highly secure and highly resilient LEO satellite digital infrastructure that delivers internet access at each designated location. The solution must satisfy the minimum characteristics, capacities, and capabilities outlined under this section.
- 8.2.2. The Service Provider shall provide all necessary CPE), including but not limited

to hardware, terminations, cabling, and auxiliary services required to establish and maintain internet connectivity.

- 8.2.3. The Service Provider shall provide, install, and commission the necessary equipment (or its equivalent integrated hardware/appliance) at each designated location for the duration of the service subscription, including but not limited to the following:

- 8.2.3.1. One (1) LEO Satellite Terminal
- 8.2.3.2. Two (2) Outdoor Access Point (Outdoor AP)
- 8.2.3.3. One (1) Indoor Access Point (Indoor AP)
- 8.2.3.4. One (1) SD-WAN Branch Router
- 8.2.3.5. One (1) Data Communication Box

- 8.2.4. The bidder shall submit the brochure/data sheet indicating technical specifications and features of the equipment during post-qualification.

8.3. CAPTIVE PORTAL

- 8.3.1. Shall provide one of the following:

- 8.3.1.1. DICTs Captive Portal – Shall require the supplier to integrate and interoperate with the DICT's Core Network Service(s) via RADIUS.

- 8.3.1.1.1. All APs should be integrated into the DICT's Captive portal via RADIUS.

- 8.3.1.1.2. DICT must give the service provider the IP address of the RADIUS server. The service provider will also configure their respective systems accordingly.

- 8.3.1.1.3. IP addressing/network design of the supplier must be approved by DICT prior to the implementation to avoid IP conflict/duplication with the existing DICT IP addressing/network.

- 8.3.2. Service Providers Captive Portal - Shall require the supplier to provide a customizable captive portal service (such as Landing Page, Authentication, End-user License Agreement, Acceptable Use Policy).

- 8.3.2.1. Captive Portal Service format, layout, and design must be approved by the DICT.

- 8.3.2.2. Must have a landing page with response time no more than five (5) seconds under full load conditions.

8.4. SIGNAGE

- 8.4.1. The Service Provider shall be responsible for the fabrication, provision, installation, and maintenance of signage for each AP location covered under this project.

- 8.4.2. The signage to be installed at each AP location shall meet the following minimum requirements:

- 8.4.2.1. Material Fabrication: The Service Signage shall be fabricated using a durable, weatherproof, and non-fading material appropriate for outdoor exposure, such as high-grade Sintra board or any equivalent material approved by the DICT.

- 8.4.2.2. Size Requirement: The print size shall be A0-size (841 mm x 1189 mm)

project signage at each site's primary location, and an A1-size [594 mm x 841mm] signage at each secondary location or directly below each AP, both mounted 1.5 – 1.7 meters above ground level, facing the main pedestrian area or other visible public space.

8.4.2.3. Compliance: The design, typography, color scheme, and layout of the Service Signage shall be approved by the DICT.

8.4.2.4. Content: The Service Signage shall clearly and legibly display the following information, as provided and approved by the DICT;

8.4.2.4.1. Contact information for technical support and service assistance.

8.4.2.4.2. Instructions on how to connect to the public Wi-Fi service.

8.4.2.4.3. Hotline numbers, QR codes, website links, and other DICT-mandated information;

8.4.2.4.4. Any additional details required by subsequent DICT issuances.

8.4.3. DICT reserves the right to require repositioning, redesign, or replacement of the signage at any time to ensure compliance with updated standards or to improve public visibility and service information.

8.4.4. The Service Provider shall perform necessary maintenance or replacement of the signage to ensure it remains legible, compliant with DICT standards, and securely mounted at all times. Damage or illegibility must be repaired or replaced within seven (7) calendar days of discovery.

8.4.5. The signage shall be installed at a distance of no less than one (1) meter and no more than ten (10) meters from the physical location of the outdoor AP.

8.5. The Service Provider shall be responsible for the coordination and acquisition of additional contact persons and details as necessary, and processing of any permits and other documentation for the survey and installation without additional cost to the DICT.

8.5.1. The DICT shall provide reasonable assistance to the Service Provider:

8.5.1.1. Initial acquisition of contact persons and details; and,

8.5.1.2. Acquisition of verbal agreement, conforme, and/or Memorandum of Agreement for the survey and installation.

8.6. MONITORING

8.6.1. The following monitoring and reporting requirements shall be interpreted collectively and not independently. All monitoring obligations shall be read together as a unified requirement for compliance.

8.6.2. The Service Provider shall provide a view access account showing a near real-time dashboard for quick status check and easier visualization of traffic, performance, and utilization.

8.6.3. The Service Provider shall implement a cloud-managed monitoring system at the LAN and routing level to visualize real-time status, track performance, and enable network logs for up to six months.

8.6.4. Monitoring shall commence from the date of acceptance of each site by DICT and shall continue for the duration of the project and as long as the location remains subscribed to the service.

8.6.5. Monitoring shall be jointly undertaken by the Service Provider and the DICT through the DICT Network Operations Center (DICT NOC) to ensure

- transparency, accountability, and compliance with the Service Level Agreement (SLA).
- 8.6.6. The AP must be compatible with, integrable into, and monitorable by the DICT Central Office - Network Monitoring System (NMS).
- 8.6.7. During the lifetime of the Project, the Service Provider shall maintain a centralized monitoring dashboard for connections monitored:
- 8.6.7.1. The cost of the system and its ongoing maintenance shall be borne entirely by the provider, at no expense to the DICT, for the duration of the project and as long as the location remains subscribed to the service.
 - 8.6.7.2. Administrative access shall be granted to the DICT.
 - 8.6.7.3. Should the implementation involve the collection or processing of personal data, both DICT and ISP/Service Provider shall ensure full compliance with Republic Act No. 10173, otherwise known as the Data Privacy Act of 2012.
 - 8.6.7.4. A Data Sharing Agreement (DSA) shall be executed between the parties in cases where personal data is to be exchanged for the purposes of monitoring and administering the Program.
 - 8.6.7.5. All such data shall be processed solely for the Project's intended purposes and safeguarded against unauthorized access or disclosure.
 - 8.6.7.6. Any third-party service provider engaged for the system shall be contractually bound to uphold the confidentiality and integrity of personal data in accordance with applicable data protection laws.
- 8.6.8. The Service Provider shall:
- 8.6.8.1. Data Analytics: Incorporate analytics tools to monitor network usage, traffic patterns, service availability, and user connectivity metrics.
 - 8.6.8.2. Reporting: Generate customizable reports for stakeholders to evaluate network performance, service utilization, and operational compliance.
 - 8.6.8.3. The Service Provider must be able to continuously monitor and report the following:
 - 8.6.8.3.1. *Status (Online/Offline)*: Real-time monitoring of whether a site or device is operational.
 - 8.6.8.3.2. *Number of Connected Users*: Tracks the total number of users currently connected to the Free Wi-Fi service.
 - 8.6.8.3.3. *Number of Unique Users*: Captures the total number of distinct users within a defined timeframe (e.g., per day).
 - 8.6.8.3.4. *Data Consumption*: Measures total inbound and outbound traffic (in MB/GB) per site.
 - 8.6.8.3.5. *Bandwidth Utilization*: Indicates the level of bandwidth usage relative to maximum available capacity.
 - 8.6.8.3.6. *Data Retention*: Ensures logs and historical data are stored based on the retention policy defined in this TOR.
 - 8.6.8.3.7. *Historical Data of Connected Users*: Including MAC addresses of users who previously connected. This should follow applicable data privacy laws (e.g., anonymization if required).
 - 8.6.8.3.8. *List of Most Visited Sites*: Aggregated report showing the top twenty (20) accessed domains or URLs. Useful for content filtering and bandwidth allocation.

- 8.6.8.4. The Service Provider shall implement centralized management through provision of a Network Monitoring System (NMS) of the operational status and data usage of each LEO kit to ensure continuous service functionality and proper tracking of data consumption. At a minimum, the following datasets shall be supported and reportable:
 - 8.6.8.4.1. Device Status – The system shall provide real-time online/offline monitoring with uptime and downtime status logs, retaining records for a minimum period of three (3) months.
 - 8.6.8.4.2. Bandwidth Utilization – Continuous monitoring and reporting of uplink and downlink bandwidth usage, with capability for per site aggregate data presentation.
 - 8.6.8.4.3. Data Consumption – Accurate measurement and reporting of total data usage per LEO kit, including daily/time-based tracking for near-limit utilization.
- 8.6.8.5. The Service Provider shall provide the Procuring Entity with administrative access credentials necessary to verify account status, data utilization, and subscription validity.
- 8.6.8.6. Upon completion of the contract, the Service Provider shall facilitate the turnover of all accounts to the Procuring Entity, either to DICT Region XIII or to the entity awarded in the succeeding procurement, without additional cost.
- 8.6.9. During the post-award delivery, testing and acceptance process, the Service Provider must be able to demonstrate monitoring of all network equipment, including APs, routers, and provide complete, ready-to-use documentation of system operations and key functionalities. The Network Monitoring System must support the following functions:
 - 8.6.9.1. Real-time and historical dashboards
 - 8.6.9.2. Customizable alerts and thresholds
 - 8.6.9.3. Role-based access controls
 - 8.6.9.4. Secure data storage and backups
 - 8.6.9.5. Exportable reports (CSV, PDF, etc.)
 - 8.6.9.6. API integration for external systems
- 8.6.10. Monitoring Compliance and Security
 - 8.6.10.1. The Service Provider shall ensure full compliance with the Data Privacy Act of 2012 and the Cybercrime Prevention Act of 2012. This compliance shall be verified during the Testing and Acceptance phase through the following verifiable parameters:
 - 8.6.10.1.1. Live Data Anonymization Validation: The Service Provider must conduct a successful technical demonstration showing that the monitoring system automatically anonymizes or masks End-User Identifiable Information (EUII), such as MAC addresses and IP addresses, within the dashboard and stored logs.
 - 8.6.10.2. All user-level data (e.g., MAC address, browsing behavior) shall be anonymized or aggregated in accordance with Republic Act No. 10173 (Data Privacy Act of 2012), and shall only be processed for legitimate project-related purposes.
 - 8.6.10.3. MAC addresses and browsing data must be handled with appropriate

consent or anonymization protocols.

- 8.6.10.4. Access to the monitoring dashboard is strictly limited to Authorized Personnel. This includes the DICT FPIAP Project Management Team, DICT-NOC engineers, and the Service Provider's designated technical leads with registered credentials.

8.6.11. Reporting and Review

- 8.6.11.1. The Service Provider is required to submit soft and hard copies of comprehensive operational reports on a monthly basis to the DICT-NOC.
 - 8.6.11.2. Periodic audits and validations should be conducted to verify system integrity and data accuracy
 - 8.6.11.3. Escalation Matrix - a structured framework to ensure the timely resolution of issues by clearly defining escalation levels, responsibilities, and time-based triggers.
 - 8.6.11.4. Service Level Agreement Report - ticket-based report created for every incident (outage or maintenance) to track the event until resolution, and it must include the reason for the outage and the actions taken to resolve the issue before the ticket is closed.
 - 8.6.11.5. Justification - formally documented explanation provided by the Service Provider for why a service outage exceeded the 72-hour restoration period, which must include valid reasons and may be validated by DICT.
 - 8.6.11.6. The Service Provider shall conduct Monthly Remote Performance Testing for all active sites, including but not limited to bandwidth throughput, uptime logs, latency, and packet loss metrics. The results shall be compiled in a Monthly Performance Report, duly signed by the Service Provider's authorized representative, and submitted together with the monthly billing document.
- 8.6.12. The DICT-NOC shall validate the submitted reports through automated monitoring tools and/or random remote verification tests, to ensure accuracy and compliance with Service Level Agreements (SLAs).

8.7. End-User Training and Operational Support

- 8.7.1. Technical, Unified Cloud, and Connectivity Management Training: The Service Provider must conduct a technical briefing for at least twenty (20) personnel from the concerned Regional Office (RO) of the DICT covering but not limited to the technical aspects of the service, operation of the Unified Cloud Management platform, and connectivity management, including real-time dashboard navigation, status monitoring, and visualization of performance and utilization metrics.
- 8.7.2. The Service Provider shall provide digital copies of the "Troubleshooting Quick-Guides" to end users.
- 8.7.3. Continuous Support: The Service Provider shall offer remote refresher briefings if significant changes are made to the monitoring dashboard or the captive portal interface.

9. TECHNICAL SPECIFICATIONS

9.1. CUSTOMER PREMISE EQUIPMENT (CPE)

9.1.1. LEO Satellite Terminal

- 9.1.1.1.** Each site must be equipped with an enterprise-grade LEO Satellite Access Terminal that offers significantly higher network priority and thermal resilience, featuring specialized hardware designed for 24/7 high-demand environments and integration with professional networking equipment listed below.
- 9.1.1.2.** The terminal must be the latest available model to ensure full compatibility with current service capabilities and hardware updates.
- 9.1.1.3. Antenna (Dish):** Must be the latest model with an electronically steered phased-array antenna.
 - 9.1.1.3.1.** Includes a kickstand (as part of the kit peripherals) and a proper mounting bracket to be environmental protection rating: Minimum IP54 (preferred: IP67).
 - 9.1.1.3.2.** Operating temperature range: -30°C to +50°C (-22°F to 122°F).
 - 9.1.1.3.3.** Requires at least 100° clear sky field of view.
 - 9.1.1.3.4.** Capable of withstanding wind speeds of at least 80 kph (50 mph).
 - 9.1.1.3.5.** AC power cable: Minimum length of 1.5 meters.
 - 9.1.1.3.6.** Data cable (proprietary or Ethernet): Minimum length of 15 meters.
 - 9.1.1.3.7.** Dish weight: Approximately 3.5–4.5 kg (7.7–9.9 lbs), excluding cables.
 - 9.1.1.3.8.** provided and installed during deployment to ensure stability and optimal antenna alignment.
- 9.1.1.4. Ethernet Connectivity:**
 - 9.1.1.4.1.** The terminal must include a built-in Ethernet LAN port to support direct wired network integration.
 - 9.1.1.4.2.** The port must support standard RJ45 Ethernet connection for seamless integration with existing networking equipment.
- 9.1.1.5. Wi-Fi Router:**
 - 9.1.1.5.1.** Must include a built-in high-performance Wi-Fi 6 (802.11ax) router.
 - 9.1.1.5.2.** Operates on dual bands (2.4GHz and 5GHz).
 - 9.1.1.5.3.** Must support mesh networking capability with compatible mesh nodes.
 - 9.1.1.5.4.** Utilizes an internal MIMO antenna configuration (minimum 3x3 or equivalent).
 - 9.1.1.5.5.** Must support WPA2 and WPA3 encryption for secure wireless connectivity.
 - 9.1.1.5.6.** Environmental protection rating: Minimum IP54, suitable for indoor use.
- 9.1.1.6. Mounting Bracket:**
 - 9.1.1.6.1.** Must include a metal roof/pole mounting kit compatible with the latest performance dish.
 - 9.1.1.6.2.** Must support adjustable tilt angles up to 120° for optimal alignment.

- 9.1.1.6.3. Designed for stable, all-weather installation on roofs or flat surfaces, with gear-adjustable lock to prevent slippage.
- 9.1.1.6.4. All-metal construction for durability and long-term outdoor use.
- 9.1.1.7. IPv6 Compliance and Network Configuration:
 - 9.1.1.7.1. The Service Provider shall ensure that the LEO Satellite network provides active IPv6 connectivity in compliance with DICT standards and the Free Wi-Fi for All Program Memorandum on IPv6 Implementation in all FPIAP-Activated Sites.
 - 9.1.1.7.2. The configuration shall support proper dual-stack or native IPv6 operation from the LEO Satellite Kit terminal up to the DICT CPEs to ensure seamless network functionality and monitoring.
 - 9.1.1.7.3. The Service Provider shall coordinate with DICT Regional Office XIII during testing and acceptance to verify IPv6 connectivity.
- 9.1.2. Outdoor Access Point
 - 9.1.2.1. Each location shall be provisioned with two (2) Outdoor APs with the following minimum specifications.
 - 9.1.2.1.1. Standard: Complies with Wi-Fi 7 (IEEE 802.11be), supporting dual-band operation on 2.4 GHz and 5 GHz frequencies, and backward compatibility with Wi-Fi 6/6E/5/4 standards.
 - 9.1.2.1.2. Speed: Provides an aggregate wireless throughput of up to 5.0 Gbps or higher utilizing up to 160 MHz channel bandwidth and 4096-QAM modulation.
 - 9.1.2.1.3. Capacity: Supports at least 500 concurrent wireless clients per access point for outdoor high-density deployments.
 - 9.1.2.1.4. Interface: One (1) 10/100/1000/2.5G BASE-T RJ-45 Ethernet port supporting IEEE 802.3af/at Power over Ethernet (PoE).
 - 9.1.2.1.5. Power: Powered via PoE with maximum power consumption not exceeding 21W under full-load operation.
 - 9.1.2.1.6. Features: Supports Multi-Link Operation (MLO), 4096-QAM, SSID-to-VLAN mapping, seamless roaming (802.11k/v/r), band steering, load balancing, mesh networking capability, captive portal authentication, and WPA2/WPA3-Enterprise wireless security.
 - 9.1.2.1.7. Management: Cloud-managed platform with centralized monitoring, configuration management, firmware upgrades, traffic analytics, remote diagnostics, and centralized cloud mesh orchestration. Subscription-free cloud management is preferred.
 - 9.1.2.1.8. Design: Outdoor-rated enclosure with minimum IP65 ingress protection rating, corrosion-resistant housing, and integrated surge/lightning protection of at least $\pm 4\text{kV}$. Access point must support pole-mounted or wall-mounted installation for long-range outdoor wireless deployments and enterprise-managed mesh environments..
 - 9.1.2.1.9. Compatible with the SD-WAN Branch Router.
 - 9.1.2.1.10. Other Requirement: With personalized DICT-marked waterproof vinyl transfer-out sticker.

9.1.3. Indoor Access Point

- 9.1.3.1.** Each location shall be provisioned with one (1) Indoor AP with the following minimum specifications.
 - 9.1.3.1.1. Standard: Complies with Wi-Fi 7 (IEEE 802.11be), supporting dual-band operation (2.4 GHz and 5 GHz), and backward compatibility with Wi-Fi 6/6E/5/4 standards. Devices must support advanced OFDMA and MU-MIMO technologies for high-density deployments.
 - 9.1.3.1.2. Speed: Must provide an aggregate wireless data rate of up to 5.0 Gbps or higher, utilizing up to 160 MHz channel bandwidth and 4096-QAM modulation.
 - 9.1.3.1.3. Capacity: Must support at least 500 concurrent wireless clients per access point in high-density environments with optimized airtime efficiency.
 - 9.1.3.1.4. Interface: One (1) 10/100/1000/2.5G BASE-T RJ-45 Ethernet port with Power over Ethernet (PoE) support compliant with IEEE 802.3af/at standards.
 - 9.1.3.1.5. Power: Powered via PoE; maximum power consumption not exceeding 21W under full load operation.
 - 9.1.3.1.6. Features: Must support Multi-Link Operation (MLO), 4096-QAM modulation, SSID-to-VLAN mapping, seamless roaming (802.11k/v/r), band steering, load balancing, mesh capability, captive portal authentication, and WPA2/WPA3-Enterprise security.
 - 9.1.3.1.7. Management: Must be cloud-managed via a centralized platform (subscription-free preferred), supporting real-time monitoring, configuration management, traffic analytics, and firmware upgrades.
 - 9.1.3.1.8. Installation: Indoor ceiling-mounted or wall-mounted form factor suitable for enterprise and high-density deployments.
 - 9.1.3.1.9. Compatible with the SD-WAN Branch Router
 - 9.1.3.1.10. Other Requirement: With personalized DICT-marked waterproof vinyl transfer-out sticker.
- 9.1.4.** SD-WAN Branch Router
 - 9.1.4.1.** Capable/Supports SNMPv2 or higher.
 - 9.1.4.2.** Shall be able to accommodate, integrate, and provide general traffic handling and management services for at least four (4) different networks via Layer 2 and Layer 3.
 - 9.1.4.3.** At least eight (8) 10/100/1000 Base-T Ports with PoE support compliant with IEEE 802.3af/at standards and compatible with the APs.
 - 9.1.4.4.** Supports routing protocols such as but not limited to Dynamic Host Configuration, Static routes, etc.
 - 9.1.4.5.** Support IEEE 802.1X/MAC/Portal authentication.
 - 9.1.4.6.** Must provide DICT with at least (2) RJ45 100Mb or higher dedicated Ethernet ports and shall be connected within the same network.
 - 9.1.4.7.** Support AAA authentication and RADIUS authentication.
 - 9.1.4.8.** Capable of blocking restricted websites.
 - 9.1.4.9.** Support up to 64 IPSEC VPN tunnels.
 - 9.1.4.10.** Support application-level traffic identification and filtering or equivalent

- 9.1.4.11. Support standard SD-WAN features, including centralized management, traffic steering, link monitoring, application-aware routing, and multi-WAN support
 - 9.1.4.11.1. Support visibility and monitoring, security integration, and centralized management
 - 9.1.4.11.2. Support on-premise connectivity controller, and element management
 - 9.1.4.11.3. Support cloud management/orchestration platform
 - 9.1.4.11.4. The Service Provider will provide SD-WAN Gateway Controller/s at the Main Office Center and provide one (1) public IP if needed.
- 9.1.5. Data Communication Box
 - 9.1.5.1. The Service Provider shall supply and install a dedicated Data Communication Box at each location to securely house all routing and networking equipment. The box must meet the following criteria:
 - 9.1.5.1.1. Minimum Size: 6U standard indoor wall-mount painted steel network cabinet.
 - 9.1.5.1.2. With clear swing-type toughened glass front door, lockable with key (4mm thick glass).
 - 9.1.5.1.3. Removable side and back panels
 - 9.1.5.1.4. Equipped with two (2) fans installed at the top for enhanced ventilation and optimal cooling
 - 9.1.5.1.5. Includes a pre-installed power distribution unit (PDU) with a 6-gang universal outlet.
 - 9.1.5.1.6. H330 x W600 x D450mm
 - 9.1.5.1.7. Thickness: 1.0mm
 - 9.1.5.1.8. Material: SPCC cold rolled steel plate
 - 9.1.5.1.9. Load Capacity: 80kg
 - 9.1.5.1.10. Protection Grade: IP20
 - 9.1.5.1.11. Color: Black
 - 9.1.5.1.12. Cantilever tray and shelves included
 - 9.1.5.1.13. With adjustable mounting rails
 - 9.1.5.1.14. Construction: Durable and tamper-resistant to protect equipment from environmental damage and unauthorized access or theft.
- 9.1.6. Uninterruptible Power Supply (UPS)- The Service Provider shall provide, install, and commission one (1) uninterruptible power supply per identified location with the following minimum specifications:
 - 9.1.6.1. Minimum 1000VA / 600W
 - 9.1.6.2. Line-Interactive with Automatic Voltage Regulation (AVR)
 - 9.1.6.3. Input Voltage Range: 162 V ~ 290 V
 - 9.1.6.4. Output Voltage Regulation (in Battery Mode): $\pm 10\%$ typical.
 - 9.1.6.5. Battery: Usually 12 V battery; e.g., 12 V / 7 Ah $\times 1$
 - 9.1.6.6. Protection: Overload, short-circuit, overcharge/discharge protection.
- 9.1.7. The solution shall support centralized management, either through a unified platform or interoperable systems capable of integrated monitoring and administration.

- 9.1.8. Installation: Positioned in a location that is secure yet accessible for routine maintenance and troubleshooting.

9.2. INSTALLATION

- 9.2.1. To ensure safety, functionality, and aesthetic quality of the installation, the Service Provider shall adhere to the following minimum standards:

- 9.2.1.1. Mounting of Equipment: Communication boxes and APs shall be securely mounted at a height of not less than six (6) feet, or at a location preferred by the beneficiary, provided such location ensures security and optimal performance.
- 9.2.1.2. Electrical Installation: All electrical components and wiring shall be installed safely and professionally, ensuring that no exposed wires or components pose any risk to personnel or property. The installation shall include a dedicated circuit breaker and proper termination to an approved electrical outlet or junction box to ensure safe, stable, and compliant power distribution.
- 9.2.1.3. Use of Materials: The use of improvised or substandard materials is strictly prohibited. This includes but is not limited to recycled plastic containers, rusted metal parts, or scrap wood. All materials used must be durable, visually appropriate, and professionally finished.
- 9.2.1.4. Cable Management: All cables shall be securely fixed, properly groomed, and not left hanging loosely. Structured cabling practices must be observed, including the installation of cable trays, plastic moldings, patch panels, and patch cables as necessary. For UTP cables, hook-and-loop fasteners are recommended; however, zip ties are acceptable where appropriate.
- 9.2.1.5. Cable Labeling: All LAN cables shall be properly labeled for easy identification, troubleshooting, and future maintenance.

- 9.3. SECURITY - Shall provide appropriate security measures and proactive solutions against attacks and malicious activities transiting through their network:

- 9.3.1. The Service Provider shall have security that blocks the proliferation of security threats, including malware, phishing, crypto mining, and Botnet command and control attacks/callbacks, as part of compliance with Republic Act 10175 or the "Cybercrime Prevention Act of 2012".
- 9.3.2. The Service provider shall have a child protection system which can block child abuse-related content, such as, but not limited to, pornography and proxies, in compliance with Republic Act 9775 or the "Anti-Child Pornography Act of 2009" and RA7610 or "Special Protection of Children Against Abuse, Exploitation and Discrimination Act" and DICT Circular No. 15, s. 2020, which prescribes the Child Online Safeguarding Policy for the Program.
- 9.3.3. The DICT may provide an updateable list of websites for blacklisting and whitelisting, and the Service Provider shall ensure the compliance for blacklisting and whitelisting of sites that the DICT may provide, or integrate

lists maintained by third parties, such as but not limited to the Internet Watch Foundation (www.iwf.org.uk), and the Philippine Government.

9.3.4. To implement the cybersecurity solution of DICT, the DNS IP addresses will be provided by the DICT Cybersecurity Bureau to be configured in the AP.

9.3.5. Content Filtering

9.3.5.1. The Service Provider shall ensure all materials are appropriate for the educational environment, free from prohibited content, and appropriate for the intended public service environment and free from prohibited content.

9.3.5.2. Prohibited content includes mobile games, online gambling, and other sites, as may be required by the Department of Information and Communications Technology (DICT).

9.4. QUALITY OF SERVICE (QOS)

9.4.1. The Service Provider shall provide policy or standards for network optimization. Must be able to provide prioritization of internet traffic between clients or applications:

9.4.2. The Service provider must ensure and maintain monthly, the required bandwidth deliverable.

10. SERVICE LEVEL AGREEMENT (SLA)

10.1. The Service Provider shall provide an industry-standard Service Level Agreement (SLA), which shall have a corresponding rebate or termination of contract in favor of the DICT should any of the following parameters are not met:

10.1.1. Safety:

10.1.1.1. Safety and proper engineering practice for the installation shall be performed as per TIA/EIA-568 B/C and NEC Guidelines

10.1.2. Availability:

10.1.2.1. Service availability of the internet service shall be 98% or above per month:

$$\text{Average Monthly Percentage Availability} = \frac{\text{Sum of all locations' percentage availability}}{\text{number of locations}}$$

10.1.2.2. Must have 24/7 technical assistance and/or help desk facilities/support service.

10.1.3. Outages:

10.1.3.1. The Service Provider shall provide a monthly service report that shows the measured bandwidth throughput, utilization, incoming and outgoing traffic, number of clients connected or unique users, and downtime per location per month.

10.1.3.2. The service provider must implement structured incident ticket-based reporting and tracking mechanisms for all incidents, such as outages or maintenance, to track reported events. A ticket shall be created when a case is raised by the DICT or a beneficiary and should remain open until the issue is resolved. The ticket closure must detail the cause of the outage and the actions taken to address it. The reporting mechanism may be manual or system-assisted, provided that it ensures completeness,

traceability, and timely reporting acceptable to DICT.

10.1.4. Retention

10.1.4.1. Deduction:

10.1.4.1.1. A total of one percent (1%) retention shall be applied to every quarterly progress payment. These quarterly deductions shall accumulate to form the total Warranty Security for the project.

10.1.4.2. Release:

10.1.4.2.1. The total accumulated retention shall be released in a single lump sum only after the expiration of the Service Operation Period, subject to:

10.1.4.2.1.1. Issuance of a Certificate of Final Acceptance;

10.1.4.2.1.2. Resolution of all pending performance issues.

10.1.4.3. Substitution:

10.1.4.3.1. As an alternative to the qu retention, the Service Provider may post a Special Bank Guarantee equivalent to at least one percent (1%) of the total contract price at the start of the project to allow for full quarterly payments without deductions.

10.1.5. Rebates:

10.1.5.1. Unavailability of service, downtimes, and/or outages affecting the delivery of connectivity service at a location shall be considered subject to rebates.

10.1.5.2. DICT reserves the right to validate and verify outage data through NOC/NMS logs and other applicable monitoring tools.; Validated downtime at the location shall be used for rebate computation.

10.1.5.3. Rebates shall not be applied if the reason for the service interruption falls under the following categories:

10.1.5.3.1. Unavailability of service, downtimes, and/or outages during scheduled maintenance, emergency maintenance, or other instances, provided that prior approval of DICT has been made at least 3 calendar days before the activity.

10.1.5.3.2. Any service outage due to force majeure (fire, earthquake, typhoon, flash floods, acts of nature, animals, or people) shall not be considered chargeable rebates and must be restored within 72 hours after the incident occurred and must be properly documented. Any outages exceeding the 72-hour period shall be regarded as chargeable rebates unless otherwise justified with proper documentation and conformed to by the Project Manager and Project Director. The computation of allowable downtime shall be based on a 24-hour, 7-day-a-week (24x7) delivery service.

10.1.5.3.3. Any downtime caused by scheduled or unscheduled power interruption or power surge will be provided with proper documentation. Scheduled maintenance must be properly coordinated and approved with the end user at least 24 hours prior to the intended activity.

10.1.5.4. In the event of service interruptions, the Service Provider shall provide rebates to the end user, subject to the availability schedule stipulated

below:

Monthly Percentage of Cumulative Service and/or Bandwidth Availability	Rebates
100.00% - 98.00%	0% of the monthly service fee
97.99% to 95.00%	5% of the monthly service fee
94.99% to 90.00%	10% of the monthly service fee
89.99% to 85.00%	15% of the monthly service fee
84.99% to 80.00%	20% of the monthly service fee
79.99% - 75.00%	25% of the monthly service fee
74.99% - 50.00%	50% of the monthly service fee
49.99% and below	100% of the monthly service fee

10.1.5.4.1. Service credits shall be granted in the form of an extension of service, which shall apply uniformly and simultaneously to all kits under each lot. The total downtime per lot shall be computed by aggregating all validated and rebatable downtime durations per AP, expressed in minutes, within the lot. The aggregate downtime shall then be divided by the total number of APs within the same lot to derive the average downtime per AP. This resulting average downtime shall serve as the basis for the corresponding service credit or service extension, which shall be applied equally and concurrently to all kits within the affected lot.

10.1.5.4.2. The Implementation of the rebate schedule is subject to the following conditions:

10.1.5.4.2.1. Computation of availability shall be based on the NMS historical alarm logs of the specific day or month under review. Computation of allowable downtime shall be based on a 24-hour, 7-day-a-week (24x7) delivery service.

10.1.5.4.2.2. Rebate shall be applied only to the site(s) extracted from the NMS historical alarm logs.

10.1.5.4.3. Additional Provision:

10.1.5.4.3.1. A Monthly Downtime Log (MDL) (refer to *Annex B*) template shall be provided by the Procuring Entity (PE) as part of the procurement documents. This template will serve as the official basis for validating reported outages and corresponding rebate computations.

10.2. Liquidated Damages (LD):

10.2.1. Locations that are not activated and accepted within the 30-day service delivery period will be subject to LD imposed on the Service Provider.

10.2.2. The applicable liquidation is at least one-tenth (1/10th) of one percent (1%) of the total cost of the unperformed portion for every day of delay until such goods/services are finally activated and accepted by the DICT.

10.2.3. For the purposes of the computation of the undelivered portion, it shall be the

total contract price over the corresponding total contracted locations, multiplied by the number of undelivered locations.

10.2.4. Such LD shall be deducted from the first payment due to the Service Provider.

10.3. Relocation:

10.3.1. In an event that locations or sites need to be relocated due to reasons such as, but not limited to, site conditions, renovation, and an approved end-user request, the Service provider shall perform a relocation without any extra cost to the DICT:

10.3.1.1. The relocation, upon the request of DICT, shall be the responsibility of the service provider. Such relocation shall be completed within a 14-day period, provided with proper documentation. Beyond the 14-day period shall be charged as rebates.

10.3.1.2. The newly nominated location must be of the same type and in close proximity to the original site or, if necessary, in the neighboring locality/province, provided that there is no existing provision of Free Wi-Fi by the Department.

10.4. Warranty

10.4.1. The Service Provider warrants that all the network components supplied under the contract are new and unused, and that they incorporate all recent improvements in design and materials, except when the technical specifications required by the DICT provide otherwise.

10.4.2. The Service Provider further warrants that all network components supplied under this contract shall have no defect, arising from design, materials, or workmanship or from any act or omission of the Service Provider that may develop under normal use of the supplied components in the conditions prevailing in the country of final destination. This warranty shall remain in effect for the entire duration of the Service Operation Period from the date of delivery and acceptance.

10.4.3. In the event that any network component is found to be faulty under normal use within the warranty periods specified below, the Service Provider shall, at no additional cost to the DICT, provide a replacement unit within five (5) calendar days for critical components and within fifteen (15) calendar days for non-critical components. Critical components refer to equipment whose failure results in total service outage or inability to deliver internet connectivity at the site; Non-critical components refer to equipment whose failure results only in partial service degradation but does not render the entire site offline. In the event of a contract renewal or extension, the warranty period shall likewise be extended to cover the entire contract duration.

10.4.4. The Service Provider shall ensure that all provided APs and SD-WAN Branch Routers fully meet the required specifications and functionalities without the need for any additional equipment. No additional devices, accessories, or add-ons shall be allowed to achieve compliance with the specifications.

10.4.5. Duration of the service contract, the Service Provider is the sole owner of the equipment used, and as such, is responsible for its maintenance and protection. In any case that the equipment has been damaged or stolen, the service

provider must replace their equipment at no additional cost to the procuring entity or to the project-identified beneficiaries.

- 10.4.6. At the end of the service contract period, the ownership of all deployed equipment in all identified lot locations — including the satellite equipment, its original kickstand, peripherals used for the service, subscription accounts, data cabinets, and all other CPEs — shall be turned over to DICT Region XIII after the completion of the service contract.
- 10.4.7. The Service Provider shall prepare and provide all the necessary and pertinent documents prior to the transfer of ownership of all the deployed equipment relative to this project, including but not limited to an inventory of all deployed equipment.
- 10.4.8. The Service Provider shall submit an inventory of all deployed CPEs, using the template provided in Annex F, together with the AAF to the Procuring Entity.
- 10.4.9. Upon contract completion, all NMS and associated super admin account(s) shall be turned over to the Procuring Entity at no additional cost. The cloud-managed monitoring system shall remain fully operational without requiring any subscription payments for the current or any succeeding years (lifetime), ensuring long-term sustainability.

10.5. Support Services:

- 10.5.1. The service provider must have dedicated personnel monitoring the network.
- 10.5.2. The Service Provider shall assign one Technical Account Manager to facilitate issue resolution.
- 10.5.3. The Service Provider shall maintain and ensure the operation of the services provided to DICT.
- 10.5.4. The Service Provider must address every incident encountered promptly and accordingly, and shall provide an escalation matrix.
- 10.5.5. The service provider must address every incident affecting the delivery of connectivity service at a location promptly and accordingly per the following SLA. All incidents, regardless of the specific component affected (e.g., APs, CPE, or related equipment), shall be treated as a single service incident per location.

10.5.5.1. First Level:

- 10.5.5.1.1. The service provider must initiate remote support to be provided within the first 30 minutes, up to one (1) hour from when the issue was first reported.
- 10.5.5.1.2. The service provider must provide on-site Support if the issue has not been resolved within the next business day after the incident was logged.

10.5.5.2. Second Level:

- 10.5.5.2.1. The service provider must provide needed repair services and parts replacement services within two (2) calendar days after the issue has been logged.
- 10.5.5.2.2. The service provider must provide configuration/re-configuration services when needed.
- 10.5.5.2.3. The Service provider must submit an Incident Management Report

not more than four (4) hours after the incident was logged and not more than twenty-four (24) hours after the issue has been resolved. Failure to comply may result in rebates.

11. OTHER REQUIREMENTS

11.1. The following requirement shall be submitted with the bid during bid submission:

11.1.1. The service provider should have undergone similar projects of a similar nature:

11.1.1.1. “Similar nature” shall be contracts pertaining to the supply, installation, configuration, commissioning, management, maintenance, and support of nationwide coverage of Low Earth Orbit Satellite internet system. The Bidder must have completed, within five (5) years prior to the deadline for the submission and receipt of bids, a Single Largest Completed Contract that is similar to the contract to be bid, and whose value, adjusted to current prices using the Philippine Statistics Authority (PSA) consumer price indices, must be at least fifty percent (50%) of the ABC.

11.2. The following requirements shall be submitted during the post-qualification period:

11.2.1. Value Added Service License – The Service Provider must be registered with the National Telecommunications Commission (NTC) as a Value Added Service Provider as defined by NTC Memorandum Circular 02-05-2008. The Certificate of Registration must be valid for the duration of the contract.

11.2.1.1. In lieu of this, the service provider may submit at least one of the following:

11.2.1.1.1. Certificate of Public Convenience and Necessity - The Service provider to submit a certification from NTC that certifies the Service Provider is authorized to operate and maintain a nationwide wired and wireless broadband network in the Philippines and to offer broadband communications services and other ancillary services.

11.2.1.1.2. Tier 1 Internet Service Provider (ISP) Certification - The Service Provider is to submit a certification from the NTC stating they are authorized to establish, install, operate, and maintain a nationwide wired and wireless broadband network in the Philippines and offer national and international broadband communication services.

11.2.2. Furthermore, in the case of a joint venture, at least one entity must be registered as a value-added service provider and an internet service provider.

11.2.3. The Service Provider must have ISO 27001 - Information Security, Cybersecurity, and Privacy Protection certification.

11.2.3.1. For joint ventures or partnerships, at least the primary Internet Service Provider or principal technology provider must possess the ISO 27001 certification.

11.2.4. The bidder must submit documentary evidence proving its status as an Authorized Reseller of LEO satellite systems, certified by the manufacturer.

11.2.5. The Service Provider must submit a list of key personnel who will be assigned to the project. This list must include: (i) at least one (1) licensed Electronics

Engineer; and (ii) technical staff, both with prior experience in implementing similar communication projects. Proof of qualifications and credentials shall be submitted, consisting of a valid Professional Regulation Commission (PRC) ID for licensed professionals and/or an official Certification of Employment/Engagement from the employer for technical staff, attesting to their relevant experience.

12. DELIVERY PERIOD/SCHEDULE OF REQUIREMENTS

- 12.1.** The delivery and installation, including testing and acceptance at all locations in the contract, must be completed within 30 calendar days upon receipt of the Notice to Proceed.
- 12.2.** The service coverage and operation shall last for six (6) months, or until December 31, 2026, whichever comes first, commencing after the service delivery and acceptance of all locations in the contracted lot.
- 12.3.** All sites activated and subsequently accepted will be paid in accordance with the payment schedule.
- 12.4.** All undelivered sites under the contract that lapse the 30-day installation and delivery schedule will be subject to LD in accordance with the provisions.
- 12.5.** In the event that the undelivered sites have been activated and subsequently accepted on any day of the subscription period, payment will only be made for the duration of actual site acceptance until the end of the contract, subject to the provisions of LD.

13. TESTING AND ACCEPTANCE

- 13.1.** DICT reserves the right to test the service and accept or reject any or all the delivered equipment and/or service not in accordance with the technical specifications.
- 13.2.** The Service Provider shall conduct testing and acceptance activity:
 - 13.2.1.** This shall be preferably in accordance with the content of the Acceptance Documents provided by the DICT, unless otherwise requested.
 - 13.2.2.** The User and Acceptance Test (UAT) shall be conducted by the authorized representatives from both parties (the DICT and the vendor).
 - 13.2.3.** The Service Provider shall accommodate at least one (1) representatives from the DICT for the duration of the testing and acceptance activities, including but not limited to transportation, meals, and accommodation, as necessary. All expenses related to the testing and acceptance activities shall be fully borne by the Service Provider and the DICT shall not be billed separately for the DICT representative and the Service Provider's travel, equipment deployment, or site visit expenses.
 - 13.2.4.** Test results, such as, but not limited to, iPerf, speed tests, or any similar bandwidth measurement tool, shall be used as proof that the supplied bandwidth is compliant with the required deliverable and is an acceptable requirement for acceptance.
- 13.3.** Testing and acceptance shall be done per the identified location:
 - 13.3.1.** Per location acceptance shall only be used for monitoring and documentation and shall not constitute full completion of the project.

- 13.3.2.** The Service Provider shall submit, together with the Service Acceptance Report, the raw (unedited) video recording that shows the following in sequence (if applicable):
 - 13.3.2.1.** Facade of the building that shows the identity of the building/location.
 - 13.3.2.2.** Walkthrough video of all the installed devices/equipment in the location.
 - 13.3.2.3.** Video recording showing GPS location (Screen recording is not allowed).
 - 13.3.2.4.** Video recording of the testing of internet service (e.g., Speedtest using Ookla, iPerf, or an equivalent network performance testing application) (Screen recording is not allowed).
- 13.3.3.** All video recordings and acceptance materials shall be submitted to the Procuring Entity through the designated web application and uploaded to a cloud-based/shared storage provided by the Service Provider. These shall be accompanied by the digitally signed User Acceptance Test (UAT) Forms and complete UAT attachment set.
- 13.3.4.** The Service Provider shall provide, maintain, and ensure uninterrupted accessibility of the cloud-based/shared storage repository where all video recordings and acceptance documents shall be uploaded, stored, and made accessible throughout the duration of the contract.
- 13.3.5.** All files shall be organized systematically, with separate folders per province, and location to ensure proper documentation, traceability, and ease of validation.
- 13.3.6.** After the acceptance of all lots, all files shall be consolidated and retained in the cloud-based/shared storage.
- 13.3.7.** The Service Provider shall be required to submit complete documentation of all installed LEO Satellites and APs and corresponding signage.
 - 13.3.7.1.** Installation Site Plan: A clear, scaled floor plan or vicinity plan for each service location, which accurately indicates the following:
 - 13.3.7.1.1.** The exact physical locations of all installed LEO Satellites and APs.
 - 13.3.7.1.2.** The corresponding physical locations of the installed signage
 - 13.3.7.1.3.** Photo Documentation File. High-resolution digital photographic evidence of each installed LEO Satellite and AP and its corresponding signage shall be submitted. Each photo must clearly show:
 - 13.3.7.1.3.1.** A close-up photograph of the installed LEO Satellites and AP, including any serial number or identifying tag;
 - 13.3.7.1.3.2.** The signage installed within the prescribed distance;
 - 13.3.7.1.3.3.** A wide-angle shot showing both AP and signage in context.
- 13.4.** The following modes of Acceptance may be undertaken:
 - 13.4.1.** On-site acceptance - End User's representative and the Service Provider's representative shall be on-site to conduct the acceptance.
 - 13.4.2.** Online acceptance / Remote Acceptance - End User's representative shall attend the acceptance online, hosted by the Service provider who is physically present onsite; or
 - 13.4.3.** Video Recorded Acceptance - The Service Provider shall conduct and record all testing procedures required for Acceptance.
- 13.5.** The Service Provider shall issue a summary of the DICT Acceptance Report, which

contains the individual date of acceptance for each location, serving as the Final Acceptance Report. The overall date of acceptance of the lot will be the final date of the lot that has been completed and accepted.

- 13.6. The Service Provider shall provide all the necessary documentation and/or specification sheets showing that the equipment provided and/or service is compliant with the specifications.
- 13.7. The Service Provider shall attach a laminated As-Built Plan for each communication box per location. This shall include the corresponding single-line network diagram covering all CPEs deployed at the site. All as-built plans, together with the required API credentials for DICT access and monitoring, shall be submitted to the Procuring Entity upon submission of the Acceptance Advisory Form (AAF).
- 13.8. Testing and acceptance shall be done per location, which include the following;

13.8.1. Internet Subscription Testing and Acceptance:

- 13.8.1.1. The acceptance of the internet subscription service shall be based on performance testing and service validation in accordance with the following criteria:
 - 13.8.1.1.1. Power-on test of the satellite terminal with successful link acquisition to the LEO satellite network.
 - 13.8.1.1.2. Connectivity test, internet speed, and latency measurements to confirm compliance with required service levels.
 - 13.8.1.1.3. Confirmation of unlimited monthly data allocation and continuous connectivity without throttling or data restrictions.
 - 13.8.1.1.4. Assessment of the centralized NMS dashboard for real-time monitoring of operational status, data usage, bandwidth allocation, and utilization.
 - 13.8.1.1.5. Validation of access credentials provided to DICT for account and service monitoring, ensuring alignment with the Terms of Reference.

13.8.2. IPv6 Compliance Testing and Validation:

- 13.8.2.1. Verification of IPv6 configuration shall be performed from the LEO terminal up to the DICT CPEs.
- 13.8.2.2. The Service Provider shall demonstrate successful dual-stack (IPv4 and IPv6) operation and confirm end-to-end IPv6 reachability.
- 13.8.2.3. IPv6 traffic transmission and routing shall be validated using standard network testing tools (e.g., ping6, traceroute6, or equivalent).
- 13.8.2.4. The Service Provider shall include in the UAT Attachment Form screenshots evidencing successful IPv6 configuration and connectivity as proof of compliance with DICT requirements.

13.9. Acceptance Procedure and Documentation:

- 13.9.1. The Service Provider shall submit an AAF at least three (3) calendar days prior to the scheduled acceptance activity (*Refer to Annex C*). Considering the multiple implementation sites, the Service Provider may submit the AAF on a partial basis, corresponding to completed and ready-for-acceptance locations. Submission of the AAF shall only be made once the site is fully operational, online, and with continuous and uninterrupted service.
- 13.9.2. Upon receipt of the AAF, the Procuring Entity shall conduct validation and shall provide an official response within three (3) working days.

- 13.9.3. In the event that submitted locations are found non-compliant or not operational, the Procuring Entity shall issue a Punch List indicating all identified site deficiencies. The Service Provider shall rectify all noted site deficiencies within seven (7) calendar days from receipt of the Punch List.
 - 13.9.3.1. If the Service Provider fails to comply within seven (7) calendar days, LD shall not yet be imposed, provided that the allowable service delivery period has not yet lapsed.
 - 13.9.3.2. Failure to complete the required rectification within the allowable service delivery period shall render the affected deliverables subject to LD, in accordance with the provisions of the TOR and applicable procurement rules and regulations.
- 13.9.4. Once a site has been submitted for acceptance and is confirmed operational, the service shall remain active and shall not be discontinued or turned off thereafter. The issuance of the Final Service Acceptance shall only be made after the completion and acceptance of all covered sites, and upon successful passing of the final acceptance activity of the last site.
- 13.9.5. The Service Provider shall prepare and submit a Service Acceptance Method of Procedure (MOP) for DICT's approval before conducting the acceptance.
- 13.9.6. The UAT form and acceptance activity shall be conducted by authorized representatives from both DICT and the Service Provider. (*Refer to Annex D*)
- 13.9.7. Upon successful testing, the Service Provider shall submit a Service Acceptance Report, subject to DICT's approval, certifying that the internet subscription service is fully operational and compliant. (*Refer to Annex E*)
- 13.9.8. The Service Provider shall furnish a Service Acceptance Report, to be approved by DICT, certifying that the service is already available and conforms in accordance with the specifications.
- 13.9.9. The Service Provider shall also submit a summary of all accepted locations, indicating the individual date of acceptance per site, which shall form part of the Final Acceptance Report. The overall acceptance date of the lot shall be the date of acceptance of the last completed site.
- 13.9.10. Final Service Acceptance shall only be issued upon completion and acceptance of all sites.

14. EXTENSION AND RENEWAL

- 14.1. Extension and Renewal, if applicable, shall be subject to the Guidelines on the Renewal of Regular and Recurring Services in the IRR of RA No. 12009.
- 14.2. Furthermore, such extension or renewal shall be subject to the availability of funds by the Procuring Entity and satisfactory performance evaluation of the Service Provider, as determined by the End-User or the Procuring Entity based on the agreed performance standards and service requirements.

15. PAYMENT SCHEDULE AND TERMS

- 15.1. Billing shall commence only after all kits under the awarded contract lot have been successfully activated, are operational, and have been accepted.

Timeline	Payment Schedule	Documents Required for Payment
The delivery of the service and acceptance at all locations in a contracted clustered lot must be completed within thirty (30) calendar days upon receipt of the NTP.	Payment scheme for the subscription shall be based on a government fiscal calendar - Quarterly: • 3rd Quarter: July - September 2026 • 4th Quarter: October - December 2026 <i>Note:</i> 1. The service coverage will officially commence the day after the successful activation and acceptance of the total contracted locations. 2. This schedule of billing is indicative and may be subject to change depending on the actual date of issuance of the PO. 3. Should the acceptance date fall in the middle of the month, a prorated computation shall be implemented. 4. Payment for the last quarter shall be put on hold unless all applicable service extensions are delivered and fulfilled. 5. Release of quarterly payments shall be subject to the submission of complete and duly validated billing documents listed under the Documents Required for Payment.	• Signed Service Acceptance Report* • User Acceptance Form (UAT) * • Quarterly Statement of Account (SOA) • Monthly Downtime Logs • Monthly Downtime Report • Monthly Service Report (SR) • Final Acceptance and Completion Certificate** • VAS License authorizing operation within Region XIII* • As-Built network diagram per location* * Applicable for first payment ** Final payment

15.2. Taxes & Other Fees – All proposals shall be inclusive of all applicable taxes, installation charges, operation and maintenance costs, incidental expenses, and other fees, including all one-time and recurring costs necessary for the full implementation and continued operation of the project.

15.3. All payments shall be processed and subject to the existing budgeting, accounting, and auditing rules and regulations of the Government of the Philippines and the DICT.

Prepared by:

Reviewed by:

JUDY ROSE E. SAGUIDON

Engineer III, Free Wi-Fi for All Program

ROLAND P. TAGANAHAN

Focal, Free Wi-Fi for All Program

Attested by:

Approved by:

ENGR. LAWRENCE P. SALANG

Chief, Technical Operations Division

MARIO P. CUÑADO

Regional Director